

AD-A156 990


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAM
LAKEPORT DAM (NH 00216..(U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 80


1/1

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 440

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|---|-----------------------|---|
| 1. REPORT NUMBER NH 00216 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Lakeport Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS | | 5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT |
| 7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION | | 6. PERFORMING ORG. REPORT NUMBER |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS | | 8. CONTRACT OR GRANT NUMBER(s) |
| 11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 12. REPORT DATE August 1980 |
| | | 13. NUMBER OF PAGES 45 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Merrimack River Basin Laconia New Hampshire Winnepesaukee River | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) ➤The dam is a concrete gravity dam with a hydraulic height of 9 ft. and totaling 222 ft. in length. The dam is in good condition. however, there are minor concerns which the NHWRB has indicated that plans for these repairs are underway. It is large in size with a high hazard potential. | | |

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

LAKEPORT DAM

NH00216

| | |
|--|----------------------|
| Accession For | |
| NTIS GRA&I <input checked="" type="checkbox"/> | |
| DTIC TAB <input type="checkbox"/> | |
| Unannounced <input type="checkbox"/> | |
| Justification | |
| By | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A/1 | 23 cut |

MERRIMACK RIVER BASIN

LACONIA, NEW HAMPSHIRE



PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: NH00216
Name of Dam: Lakeport Dam
City: Laconia
County and State: Belknap County, New Hampshire
River: Winnepesaukee River
Date of Inspection: July 9, 1980


BRIEF ASSESSMENT

Lakeport Dam is a concrete gravity dam with a hydraulic height of 9 feet and totaling 222 feet in length. The dam consists of a 15-foot stoplog spillway structure at the southeast end, an overflow spillway totaling 72 feet in length, a gated section 78 feet in length which consists of three 10'H x 18'W gates, and a 57-foot long concrete retaining wall at the northwest abutment. The dam impounds a reservoir of large size with a maximum usable storage capacity of 165,800 acre-feet. Lake Winnepesaukee has a surface area of about 73 square miles and forms the largest recreational lake in the State of New Hampshire. The drainage area to the dam consists of 363 square miles of hydrologically diverse elements.

The dam is in good condition. Minor concerns are an eroded area on the downstream southeast abutment training wall, surface spalling on the walls of the intake channel to the stoplog spillway, and a minor sinkhole behind the dry-stone-masonry training wall on the northwest side of the discharge channel about 35 feet downstream of the dam. The NHWRB has indicated that plans for these repairs are underway.

Lakeport Dam is large size and high hazard classification based on storage volume and potential for loss of 4 or more lives and excessive property damage in event of a breach. In accordance with the Recommended Guidelines for Safety Inspection of Dams, the test flood is required to be the Probable Maximum Flood (PMF). The PMF inflow was determined to be 218,000 cfs with a runoff of 13.6 inches. Routing of this inflow was determined to raise the level of Lake Winnepesaukee to 509' NGVD. Backwater analysis indicates a drop of 3.8 feet from the lake surface to Lakeport Dam at this elevation. The elevation at Lakeport Dam was determined to be 505.2' NGVD with a discharge of 5,100 cfs. All gates were assumed to be fully opened during a flooding event of this magnitude. The test flood analysis indicates the dam would be overtopped during the PMF by slightly less than one foot. The northwest abutment would not be overtopped. The total discharge capacity of the structure at top of dam is 4,117 cfs which is 81 percent of the routed test flood outflow.

The owner, the New Hampshire Water Resources Board, should implement the recommendations and remedial measures given in Sections 7.2 and 7.3 within two years after receipt of this Phase I inspection report.


Warren A. Guinan, P.E.
Project Manager
N.H. P.E. 2339

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation: however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

| <u>Section</u> | <u>Page</u> |
|-----------------------|-------------|
| Letter of Transmittal | |
| Brief Assessment | |
| Review Board Page | |
| Preface | i |
| Table of Contents | ii-iv |
| Overview Photo | v |
| Location Map | vi |

REPORT

1. PROJECT INFORMATION

| | |
|---|-----|
| 1.1 General | 1-1 |
| a. Authority | 1-1 |
| b. Purpose | 1-1 |
| 1.2 Description of Project | 1-1 |
| a. Location | 1-1 |
| b. Description of Dam and Appurtenances | 1-2 |
| c. Size Classification | 1-3 |
| d. Hazard Classification | 1-3 |
| e. Ownership | 1-4 |
| f. Operator | 1-4 |
| g. Purpose of Dam | 1-4 |
| h. Design and Construction History | 1-4 |
| i. Normal Operating Procedures | 1-4 |
| 1.3 Pertinent Data | 1-5 |
| a. Drainage Area | 1-5 |
| b. Discharge at Damsite | 1-5 |
| c. Elevation | 1-5 |
| d. Reservoir | 1-6 |
| e. Storage | 1-6 |
| f. Reservoir Surface | 1-6 |
| g. Dam | 1-7 |
| h. Diversion and Regulating Tunnel | 1-7 |
| i. Spillway | 1-7 |
| j. Regulating Outlets | 1-7 |

| <u>Section</u> | <u>Page</u> |
|---|-------------|
| 2. ENGINEERING DATA | |
| 2.1 Design | 2-1 |
| 2.2 Construction | 2-1 |
| 2.3 Operation | 2-1 |
| 2.4 Evaluation | 2-1 |
| a. Availability | 2-1 |
| b. Adequacy | 2-1 |
| c. Validity | 2-1 |
| 3. VISUAL INSPECTION | |
| 3.1 Findings | 3-1 |
| a. General | 3-1 |
| b. Dam | 3-1 |
| c. Appurtenant Structures | 3-2 |
| d. Reservoir | 3-3 |
| e. Downstream Channel | 3-3 |
| 3.2 Evaluation | 3-3 |
| 4. OPERATIONAL AND MAINTENANCE PROCEDURES | |
| 4.1 Operational Procedures | 4-1 |
| a. General | 4-1 |
| b. Description of Any Warning System in Effect | 4-1 |
| 4.2 Maintenance Procedures | 4-1 |
| a. General | 4-1 |
| b. Operating Facilities | 4-1 |
| 4.3 Evaluation | 4-1 |
| 5. EVALUATION OF HYDROLOGIC/HYDRAULIC FEATURES | |
| 5.1 General | 5-1 |
| 5.2 Design Data | 5-1 |
| 5.3 Experience Data | 5-1 |
| 5.4 Test Flood Analysis | 5-2 |
| 5.5 Dam Failure Analysis | 5-2 |

| <u>Section</u> | <u>Page</u> |
|---|-------------|
| 6. EVALUATION OF STRUCTURAL STABILITY | |
| 6.1 Visual Observations | 6-1 |
| 6.2 Design and Construction Data | 6-1 |
| 6.3 Post Construction Changes | 6-1 |
| 6.4 Seismic Stability | 6-1 |
| 7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES | |
| 7.1 Dam Assessment | 7-1 |
| a. Condition | 7-1 |
| b. Adequacy of Information | 7-1 |
| c. Urgency | 7-1 |
| 7.2 Recommendations | 7-1 |
| 7.3 Remedial Measures | 7-1 |
| a. Operating and Maintenance Procedures | 7-1 |
| 7.4 Alternatives | 7-2 |


APPENDIXES

| | |
|--|-----|
| APPENDIX A - VISUAL INSPECTION CHECKLIST | A-1 |
| APPENDIX B - ENGINEERING DATA | B-1 |
| APPENDIX C - PHOTOGRAPHS | C-1 |
| APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS | D-1 |
| APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS | E-1 |




Photo 1 - Overview of Lakeport Dam.

July 10, 1980



Reprinted by permission of the Department of Resources and Economic Development, Concord, N.H. 03301, and the copyright owners, The National Survey, Chester, VT. 05143. 5/18/79

SCALE IN MILES



MAP BASED ON STATE OF NEW HAMPSHIRE OFFICIAL HIGHWAY MAP.

Anderson-Nichols & Co., Inc.

CONCORD

NEW HAMPSHIRE

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

LAKEPORT DAM LOCATION MAP

WINNIPESAUKEE RIVER

NEW HAMPSHIRE

SCALE: SEE BAR SCALE

DATE: AUGUST 1980

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
LAKEPORT DAM

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols under a letter of March 22, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0050, as changed, has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Lakeport Dam is located in the Village of Lakeport within the city limits of Laconia, New Hampshire. The dam is located between Paugus and Opechee Bays, about 4.4 miles downstream of the origination of the Winnepesaukee River at the outlet of Lake Winnepesaukee at the Weirs. Lakeport Dam, although located downstream of the outlet, controls the water level and outflow of Lake Winnepesaukee. Lakeport Dam is located on the Winnepesaukee River approximately 7.6 miles upstream of the rivers' confluence with the Pemigewasset River. The Merrimack River originates at the confluence of the Winnepesaukee and Pemigewasset Rivers in Franklin, New Hampshire. Lakeport Dam is shown on USGS 15-minute Quadrangle, Winnepesaukee, New Hampshire with coordinates approximately at N 43° 32' 54", W 71° 27' 57". The City of Laconia is located in Belknap County, New Hampshire. (See Location Map, page vi.)

b. Description of Dam and Appurtenances. Lakeport Dam is a concrete gravity dam totaling 222 feet in length with a hydraulic height of 9 feet and a structural height of 10 feet. The dam consists of four sections which from the southeast to the northwest abutment, are:

(1) A stoplog gated structure about 15 feet in length with two bays of stoplogs each about 5 feet in length separated by a steel support pier. This stoplog structure is located on the site of an old canal.

(2) The concrete uncontrolled overflow spillway structure, which adjoins the end of the gated section, totals 72 feet in length. The spillway and piers are of the original stone construction, now capped over with concrete. The spillway itself consists of three 15-foot ± wide bays separated by two 10-foot center piers. The crest is 2 feet in width with a total effective weir length of 62 feet. The downstream face slopes at approximately 1'H:0.7'V then continues to a concrete slab about 10 feet in length and 6 inches thick.

The flow through the stoplog spillway and over the overflow spillway discharges into a side channel 13 feet wide and about 50 feet long that runs parallel to the axis of the dam. The floor of this channel is wooden plank. Some discharge is maintained over the stoplogs to keep this planking wet to prevent deterioration. The wall opposite the spillways is stone masonry. This side channel discharges into the main channel.

(3) The gated section, totaling 78 feet in length, consists of three bays, each 18 feet wide, separated by six-foot wide circular nose concrete piers. The floor of each bay is a concrete slab 2 feet thick. The gate sill is a six-inch steel beam with the top flange set flush with the surface of the concrete floor. The three gates are 18'W x 10'H steel skin plated gates which are electrically operated. The gate hoisting mechanism for each gate is operated by an electric motor mounted on the top of a 14½-foot high steel frame super-structure. The motor is operated by a push button located on the southwesterly super-structure column nearest each gate. Electric power is supplied by the Public Service Company of New Hampshire through a main switch in the auxiliary power building which, in turn, is connected to a control panel located on the northwest end of the gated section. Power is also supplied through the control panel to three gate heaters on each gate. Two of the heaters are installed on the gate seals and the third is a sill heater. In case of failure of the normal power supply, a 25 kw Onan generator in the auxiliary power building is available to furnish electric power.

(4) The northwest abutment is formed by a retaining wall extending 57 feet from the end of the gated structure. The wall is the original stone block retaining wall which was later faced on the upstream side with an 18-inch thick reinforced concrete wall. The area is filled with earth and planted in grass.

The main downstream channel averages about 75 feet in width. The westerly stone masonry channel wall extends downstream approximately 190 feet. The east stone masonry channel forms a junction with the side channel wall and extends downstream for approximately 140 feet. The floor of the channel is covered with wood planking for a distance of about 70 feet downstream of the gated section of the dam. Discharge flows into Opechee Bay about 300 feet downstream of the dam.

c. Size Classification. Large (hydraulic height - 9 feet; storage - 165,800 acre-feet) based on storage ($\geq 50,000$ acre-feet) as given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. The downstream hazard that would result from a failure of Lakeport Dam was estimated using the procedure set forth in "Rule of Thumb Guidelines for Estimating Downstream Dam Failure Hydrographs", Corps of Engineers, New England Division, April 1978.

A major breach of the dam was analyzed with pool elevation at 504.32' NGVD and with the dam discharging the normal recreational flow of about 250 cfs. The breach was assumed to occur at either the gated or spillway section of the dam. Both assumed breach conditions would result in a breach discharge in the range of 3,600-3,730 cfs. The flow value is comparable to the 100-year flow of 3,500 cfs used in Reference 2 (see 5.1 b.). Therefore, the profile developed with this discharge provides a reasonable estimate of downstream damage potential should the dam fail at top of dam. A breach discharge of this magnitude could cause an increase in stage of about 3.5 feet on Opechee Bay, or cause the bay to rise to approximately 495.5' NGVD. Correspondence from the NHWRB indicates that flooding would occur on the shores of Opechee Bay with elevation at 494' NGVD. The breach wave itself would be attenuated in Opechee Bay but the flooding discharge would continue downstream into downtown Laconia. According to the files of the NHWRB and confirmed by the references, the maximum safe discharge capacity of the constricted channel in downtown Laconia is 2,600 cfs. Any discharge above this would cause substantial damage. There is a potential for loss of 4 or more lives in this area, especially if a breach occurred without warning. Surcharge storage on Winnisquam Lake would significantly attenuate the flooding conditions. Thus, no significant damages below Winnisquam are anticipated. Lakeport Dam was classified High Hazard based on excessive property damage and potential for loss of 4 or more lives in event of a breach. A detailed downstream hazard map can be seen in Appendix D.

e. Ownership. The earliest recorded ownership was by the Winnipissiogee Lake Cotton and Woolen Manufacturing Company in 1851. Ownership was passed to the Public Service Company of New Hampshire in 1943 and then to the State of New Hampshire Water Resources Board (NHWRB) on March 31, 1958. The current owner is the NHWRB, 37 Pleasant Street, Concord, New Hampshire 03301. Phone: (603) 271-3406.

f. Operator. Mr. Bob Fay, under direction of the NHWRB, is responsible for the operation of Lakeport Dam. Mr. Fay's address is 93 Elm Street, Lakeport, New Hampshire 03246. Phone: (603) 524-1260/9194.

g. Purpose of Dam. Under ownership by the Winnipissiogee Lake Cotton and Woolen Manufacturing Company, the dam was used to create water storage for mills in Lowell and Lawrence, Massachusetts. Records indicate that a building near the damsite used the impoundment for hydro-electric power generation and was removed from service in 1932. The Public Service Company of New Hampshire utilized the dam and its impoundment for storage. After the reconstruction in 1958, no generating capacity was installed. Today, the dam and its impoundment form the largest recreational lake in the State of New Hampshire as well as supply downstream water users.

h. Design and Construction History. No information was found regarding the original design and construction of the dam. The dam was believed to have been constructed or reconstructed by the Winnipissiogee Lake Cotton and Woolen Manufacturing Company in 1851. The dam at this time consisted of a timber structure. Under ownership by the Public Service Company of New Hampshire the dam was rebuilt in 1957-1958. A complete set of design plans is available in the files of the NHWRB. Plans pertinent to this study can be seen in Appendix B. The first plan shown in Appendix B shows the conditions at the dam prior to the 1957-1958 reconstruction. Correspondence from the NHWRB indicates that the Scott & Williams Canal was taken out and the stoplog bay constructed in its place sometime in 1967.

i. Normal Operating Procedures. The NHWRB operates Lakeport Dam in conjunction with Avery Dam on the Winnepesaukee River in downtown Laconia, and Lochmere Dam on Lake Winnisquam. Avery and Lochmere Dams are also owned and operated by the NHWRB. Bob Fay, under direction of the NHWRB, is responsible for the operation of all three dams. The dams are visited at least every other day and gage readings at Lakeport are reported to the NHWRB. Engineers at the NHWRB, in turn, direct any gate operations necessitated by the operator's input. The dam operator lives near and within sight of Lakeport Dam and visits the dam more often if the need is indicated.

Lakeport Dam itself is operated to provide maximum recreational benefits. However, in the contract of sale from the Public Service Company and the NHWRB, it was stipulated that the NHWRB

shall maintain as high a discharge of water from Lakeport Dam as is possible, subject to reasonable use for the recreational interests of the lake. The NHWRB, therefore, provides a minimum discharge of 250 cfs for downstream water users who pay the cost of operation.

1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 363 square miles (232,320 acres) of various terrain. The normal recreational surface area of Lake Winnepesaukee is 73 square miles which constitutes 20 percent of the watershed. The drainage area is comprised of hydrologically diverse elements. The outlet of Lake Winnepesaukee at the Weirs, about 4.4 miles upstream of Lakeport Dam, contains a drainage area of 351 square miles. Outflow through the constricted channel at the Weirs discharges into Paugus Bay. Lakeport Dam is situated in the constricted channel between Paugus and Opechee Bays.

b. Discharge at Damsite

(1) Outlet works - three (3) 18'W x 10'H, vertical lift gates at invert elevation 495.22' NGVD. Gate discharge capacity (one gate) at top of dam - 1360 cfs @ 504.32' NGVD. Combined capacity (3 gates) - 4080 cfs @ 504.32' NGVD.

(2) The maximum known flood at the damsite occurred on March 31, 1936 when a maximum discharge of 2,890 cfs was recorded.

(3) Ungated spillway capacity at top of dam - 6 cfs @ 504.32' NGVD.

(4) Ungated spillway capacity at test flood elevation - 185 cfs @ 505.2' NGVD.

(5) Gated spillway capacity at top of dam elevation - 30 cfs @ 504.32' NGVD (assuming stoplogs @ 503.4' NGVD)

(6) Gated spillway capacity at test flood elevation - 80 cfs @ 505.2' NGVD (assuming stoplogs @ 503.4' NGVD)

(7) Total spillway capacity at test flood elevation - 265 cfs @ 505.2' NGVD

(8) Total project discharge at top of dam - 4117 cfs @ 504.32' NGVD

(9) Total project discharge at test flood elevation - 5100 cfs @ 505.2' NGVD

c. Elevation (ft. above NGVD based on plans and information found in the files of the NHWRB)

(1) Streambed at toe of dam (gate invert) - 495.22

- (2) Bottom of cutoff - unknown
- (3) Maximum tailwater - unknown
- (4) Normal pool - 504.22±
- (5) Full flood control pool - not applicable
- (6) Spillway crest - 504.22 (ungated)
- 503.40 (gated)
- (7) Design surcharge (original design) - unknown
- (8) Top of dam - 504.32
- (9) Test flood surcharge - 505.2

d. Reservoir (Length in miles)

- (1) Normal pool - 17.5
- (2) Flood control pool - not applicable
- (3) Spillway crest pool - 17.5
- (4) Top of dam - 17.5
- (5) Test flood pool - 17.5

e. Storage (acre-feet) Usable storage capacity at USGS gage.

- (1) Normal pool - 165,800
- (2) Flood control pool - not applicable
- (3) Spillway crest pool - 165,800
- (4) Top of dam - 165,800
- (5) Test flood pool - 208,000

f. Reservoir Surface (square miles)

- (1) Normal pool - 73
- (2) Flood control pool - not applicable
- (3) Spillway crest - 73
- (4) Test flood pool - 73
- (5) Top of dam - 73

g. Dam

(1) Type - concrete gravity dam with gated section, overflow spillway, and stoplog spillway structure.

(2) Length - 222'

(3) Height - 10' (structural); 9' (hydraulic)

(4) Top Width - varied

(5) Side Slopes - varied

(6) Zoning - unknown

(7) Impervious core - unknown

(8) Cutoff - available design drawings indicate a sheet pile cutoff wall

(9) Grout curtain - unknown

h. Diversion and Regulating Tunnel - not applicable

i. Spillway

(1) Type - uncontrolled overflow; stoplog structure

(2) Length of weir - 62'; 10'

(3) Crest elevation - 504.22' NGVD; 503.4' NGVD

(4) Gates - none

(5) U/S Channel - Paugus Bay, which originates at the outlet of Lake Winnepesaukee at the Weirs, is about 4.4 miles in length and ends at Lakeport Dam. The Elm Street Bridge and a USGS gaging station are located immediately upstream of the dam.

(6) D/S Channel - Discharge from the damsite flows approximately 300 feet downstream where it empties into Opechee Bay. The elevation drop through this reach is about 3 feet. The discharge channel at the damsite consists of stone masonry walls which extends downstream 190 feet on the northwest side and 140 feet on the southeast side.

j. Regulating Outlets

(1) Invert - 495.22' NGVD

(2) Size - three (3) 18' W x 10' H

(3) Description - vertical lift gates

(4) Control Mechanism - gate hoisting mechanism for each gate operated by an electric motor

(5) Other - three heaters are installed on each gate. Two of the heaters are installed on the gate seals and the third is a sill heater.

SECTION 2 ENGINEERING DATA

2.1 Design

No design data were found for the original Lakeport Dam. A complete set of design drawings for the 1957-58 reconstruction by the Public Service Company of New Hampshire were found in the files of the New Hampshire Water Resources Board (NHWRB). Those plans pertinent to this study can be seen in Appendix B.

2.2 Construction

No construction records were noted. However, the design drawings were noted "Revised - As built".

2.3 Operation

No operational engineering data were found.

2.4 Evaluation

a. Availability. Information found in the files of the NHWRB included complete 1957-58 reconstruction design plans, operating procedures and historical data on the dam and Lake Winnepesaukee.

b. Adequacy. The information found in the files of the NHWRB and past studies done on the Winnepesaukee River basin, in conjunction with the inspection and hydrologic/hydraulic analyses done for this report, are sufficient to determine the final assessments and recommendations of this investigation.

c. Validity. The majority of the collected data was validated by this study.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General. Lakeport Dam is a low run-of-river dam which impounds a reservoir of large size. The watershed above the reservoir is moderately to steeply sloping and wooded. The downstream area is moderately sloping.

b. Dam. Lakeport Dam is a concrete gravity dam totaling 222 feet in length with a hydraulic height of 9 feet and a structural height of 10 feet. (See Appendix C - Photos 2 & 3.) The dam consists of four sections which from the southeast to the northwest abutment, are:

(1) A stoplog gated structure about 15 feet in length with two bays of stoplogs each about 5 feet in length separated by a steel support pier. (See Appendix C - Photo 4.) This stoplog structure is located on the site of an old canal.

(2) The concrete uncontrolled overflow spillway structure, which adjoins the end of the gated section, totals 72 feet in length. The spillway itself consists of three 15 ft. \pm wide bays separated by two 10-ft. center piers. The crest is 2 feet in width. The downstream face slopes at approximately 1'H:0.7'V then continues to a concrete slab about 10 feet in length and 6 inches thick. (See Appendix C - Photo 5.)

The flow through the stoplog spillway and over the overflow spillway discharges into a side channel 13 feet wide and about 50 feet long and runs parallel to the axis of the dam. (See Appendix C - Photo 6.) The floor of this channel is wooden plank. Some discharge is maintained over the stoplogs to keep this planking wet to prevent deterioration. The wall opposite the spillways is stone masonry. This side channel discharges into the main channel.

(3) The gated section, totaling 78 feet in length, consists of three bays, each 18 feet wide, separated by six-foot wide circular nose concrete piers. (See Appendix C - Photo 7.) The three gates are 18'W x 10'H steel skin plated gates which are electrically operated.

(4) The northwest abutment is formed by a retaining wall extending 57 feet from the end of the gated structure. (See Appendix C - Photo 8.) The wall is the original stone block retaining wall which was later faced on the upstream side with an 18-inch thick reinforced concrete wall. The area is filled with earth and planted in grass.

The southeast abutment consists of soil. No evidence of leakage around the end of the dam was observed. The northwest abutment also consists of soil. Because of grading which was apparently done on this abutment when the concrete gate structure was built it is not possible to identify on the basis of the visual inspection alone where the contact is between the backfill next to the gate structure and the natural abutment soil. A concrete wall retains the upstream side of the abutment soil. Three vertical hairline cracks were observed in this wall. No evidence of leakage around the northwest end of the dam was observed. (In an inspection report dated July 1978 Chas. T. Main, Inc. noted minor leakage discharging downstream of Pier #7 of the gate structure at the northwest abutment, but no seepage was observed at that location at the time of the present inspection.)

c. Appurtenant Structures. The stoplog gated structure, located at the southeast end of the dam, is in fair condition. The top stoplogs appeared to be in good condition; the bottom stoplogs show deterioration and several are leaking. The steel supports were observed to have corroded surfaces. At the top of the stoplog structure at the intake channel the concrete walls are spalled. (See Appendix C - Photos 9 & 10.) Downstream of the stoplog structure on the southeast abutment training wall, the bottom 3 feet of the wall is eroded with reinforcing steel visible. (See Appendix C - Photo 11.) The maximum depth of erosion was observed to be about 6 inches.

A concrete uncontrolled overflow spillway structure is adjacent to the stoplog structure and totals 72 feet in length. The concrete appeared to be in good condition with no visible spalling or staining.

The gated section was found to be in generally good condition with only minor surface erosion on the bottom of the downstream pier walls. The gates themselves consist of three (3) 18'W x 10'H vertical lift gates. Some leakage was observed around the ends of the gates. (See Appendix C - Photo 12.) On the steel components, minor spot rusting was observed. The embedded gate supports were surface rusted. The three gates are electrically operated. Each gate has a 2-hp, 208-volt, 3-phase motor. All three gates were opened and closed without difficulties. In addition, each gate has 2.5-kW, 208-volt, 3-phase side sill heaters and seal heaters. All motors and heaters are in good condition. The existing 200-A, 120/180-volt service in the generator house is in good condition. There is a manual double throw switch to transfer to emergency power. The emergency power consists of a 25-kW LPG Fuel Onan generator that is in good condition. The emergency generator was started and was up to full output in eight seconds. This generator is manually exercised once each month by operating personnel. All conduit, panel boards, wiring, lighting fixtures, etc. appeared to be in good condition.

A wood deck tailrace exists downstream of the gated section and runs for about 70 feet downstream. The wood facing is deteriorated and eroded on the surface and at joints. All planking appeared to be intact.

The wooden walkway (service bridge) was in generally good condition with some deteriorated planks. The dam operator indicated during the inspection that the portion of the wooden walkway between the stoplog structure and the gated structure was soon to be removed. This is being done in an effort to curb vandalism at the dam.

d. Reservoir. Lakeport Dam is the control structure for regulating the level of Lake Winnepesaukee, and is located at the southern end of Paugus Bay. The watershed above Lake Winnepesaukee is moderately to steeply sloping and wooded. The lake is not subject to significant sedimentation. Elm Street Bridge and a USGS gate is located immediately upstream of the dam. (See Appendix C - Photo 13.)

e. Downstream Channel. Dry-stone-masonry training walls are located on both sides of the downstream discharge channel. (See Appendix C - Photos 14 & 15.) One minor sinkhole was noted in the fill behind the training wall on the northwest side of the channel about 35 feet downstream from the dam. (See Appendix C - Photo 16.) This sinkhole appears to be the result of fill behind the wall being washed out by rain-water through the spaces between the rock blocks. A sinkhole behind the training wall on the southeast (left) side of the downstream channel (which was noted in the July 1978 inspection report prepared by Chas. T. Main, Inc.) has apparently been filled in. Minor amounts of relatively fresh placed backfill apparently have been placed behind the downstream training walls at various locations, apparently where fill had washed out through the spaces between the rock blocks. It does not appear that the sinkholes have any adverse effects on the integrity of the dam.

A timber apron covers the bottom of the channel immediately downstream of the dam for about 70 feet. Farther downstream the channel bottom is covered with sand, gravel, and boulders. The downstream channel discharges into Opechee Bay about 300 feet downstream from the dam. A few trees overhang the southeast side of the channel.

3.2 Evaluation

Based on the results of the visual inspection, Lakeport Dam is considered to be in good condition.

A minor sinkhole behind the training wall on the northwest side of the discharge channel could result in localized failure of the training wall if it is allowed to increase in size.

The eroded area on the downstream southeast abutment training wall, if left uncorrected, could effect the integrity of the training wall itself but not effect the integrity of the dam.

The surface spalling on the intake channel of the stoplog spillway does not pose a threat to the integrity of the dam.

SECTION 4
OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedures

a. General. The New Hampshire Water Resources Board (NHWRB) operates Lakeport Dam in conjunction with Avery Dam on the Winnepesaukee River in downtown Laconia and Lochmere Dam on Lake Winnisquam, all of which are owned and operated by the NHWRB. Bob Fay, under direction of the NHWRB, is responsible for the operation of all three dams. The dams are visited at least every other day and gage readings at Lakeport are reported to the NHWRB. Engineers at the NHWRB, in turn, direct any gate operations necessitated by the operator's input. The dam operator lives near and within sight of Lakeport Dam and visits the dam more often if the need is indicated.

Lakeport Dam itself is operated to provide maximum recreational benefits as well as provide sufficient discharge for use by downstream water owners who pay for the cost of operation. The maximum regulated flow from the lake is not to exceed 250 cfs between June 1 and October 15 when the level in Lake Winnepesaukee is equal to or less than 502.4'NGVD.

b. Description of Any Warning System in Effect. No formal warning system was found. In case of an emergency, the NHWRB may grant permission to release more than 250 cfs during June 1 to October 15.

4.2 Maintenance Procedures

a. General. Lakeport Dam is visited at least every other day. At that time, conditions at the dam are checked and reported to the NHWRB.

b. Operating Facilities. The dam has three electrically operated gates which are operated periodically. The emergency generator is manually exercised once each month by operating personnel. An operating manual for the generator and gates was at the dam site at the time of the inspection.

4.3 Evaluation

The current operational and maintenance procedures appear satisfactory to ensure that any minor problems encountered can be remedied within a reasonable period of time.

SECTION 5
EVALUATION OF HYDROLOGIC/HYDRAULIC FEATURES

5.1 General

Lakeport Dam controls the water level and outflow of Lake Winnepesaukee, the largest recreational lake in the State of New Hampshire. The drainage area consists of 363 square miles of hydrologically diverse elements. The lake surface area consists of 73 square miles and the peripheral contiguous area constitutes the additional 290 square miles. Lakeport Dam is a concrete gravity dam with a hydraulic height of 9 feet. The dam is actually located 4.4 miles downstream of the outlet of Lake Winnepesaukee at the Weirs. After discharging through the constricted channel at the Weirs, flow enters Paugus Bay. Lakeport Dam is located at a constricted channel downstream of Paugus Bay.

5.2 Design Data

The available data pertinent to the Lakeport Dam comes from four primary sources:

(1) The New Hampshire Water Resources Board (NHWRB) files on the dam;

(2) the backup files for the City of Laconia Flood Insurance Study, prepared for the Federal Insurance Administration by Anderson-Nichols & Company, Inc. (ANCo) of Concord, New Hampshire;

(3) "Lakeport Dam Inspection and Analysis Report", prepared for the NHWRB by Chas. T. Main, Boston, Massachusetts, July 1978; and

(4) Hydraulic Engineering Analysis for Evaluating Flood Stage Reduction on the Winnepesaukee River, New Hampshire, prepared by ANCo for the Corps of Engineers, New England Division, December 1978.

5.3 Experience Data

The maximum known flood at the damsite occurred on March 31, 1936 when a maximum discharge of 2,890 cfs was recorded. The maximum lake level recorded was 505.88' NGVD in May 1954. This was before the 1957-1958 reconstruction. Correspondence from the NHWRB indicates that Lakeport Dam was overtopped July 6, 1973 when the discharge was recorded to be 2,430 cfs. The three gates were each opened 42" and the overtopping elevation was 505.33' NGVD.

5.4 Test Flood Analysis

Lakeport Dam was classified as being large in size having a hydraulic height of 9 feet and a maximum storage capacity of 165,800 acre-feet. The dam was determined to have a high hazard classification. Using the Recommended Guidelines for Safety Inspection of Dams, the test flood was required to be the Probable Maximum Flood (PMF).

The test flood inflow cannot simply be determined by use of the PMF guide curves due to the complexity of the hydrologic and hydraulic conditions which comprise the Winnepesaukee River drainage basin. A detailed PMF analysis was performed in Reference 3 (see 5.1 b.) taking into account the individual hydrologic response characteristics of hydrologically diverse elements which comprise the watershed. This study was reviewed and determined to be a more detailed study than that warranted under the scope of a Phase I report. Therefore, the PMF analysis was utilized for this report and can be seen in Appendix D.

To determine the PMF inflow, the drainage area was separated into the lake area (73 square miles) and the peripheral contiguous area (290 square miles). A unit hydrograph was produced which had a peak PMF inflow of 218,000 cfs and a total runoff volume of 13.6 inches. Routing of this inflow was determined to raise the level of Lake Winnepesaukee to elevation 509' NGVD. Backwater analysis indicates a drop of 3.8 feet from the lake surface to Lakeport Dam at this elevation. Therefore, the elevation at Lakeport was determined to be 505.2' NGVD with a discharge of 5,100 cfs. The rating curve for Lakeport Dam was calculated assuming all gates fully opened. It is the opinion of the NHWRB that the maximum allowable overtopping of the dam at the northwest abutment is one foot. Beyond this the integrity of the structure is questionable. Therefore, during a storm of this magnitude, all gates would be fully opened in order to protect the structure from overtopping failure.

The test flood analysis indicates that the dam would be overtopped during the PMF by 0.88 feet. The northwest abutment would not be overtopped. The total discharge capacity of the structure is 4,117 cfs which is 81 percent of the routed test flood outflow.

5.5 Dam Failure

The downstream hazard that would result from a failure of Lakeport Dam was estimated using the procedure set forth in "Rule of Thumb Guidelines for Estimating Downstream Dam Failure Hydrographs", Corps of Engineers, New England Division, April 1978.

A major breach of the dam was analyzed with pool elevation at 504.32' NGVD and with the dam discharging the normal recreational flow of about 250 cfs. The breach was assumed to occur at either the gated or spillway section of the dam. Both assumed breach conditions would result in a breach discharge in the range of 3,600-3,730 cfs. The flow value is comparable to the 100-year flow of 3,500 cfs used in Reference 2 (see 5.1 b.). Therefore, the profile developed with this discharge provides a reasonable estimate of downstream damage potential should the dam fail at top of dam. A breach discharge of this magnitude could cause an increase in stage of about 3.5 feet on Opechee Bay or cause the bay to rise to approximately 495.5' NGVD. Correspondence from the NHWRB indicates that flooding would occur on the shores of Opechee Bay with elevation at 494' NGVD. The breach wave itself would be attenuated in Opechee Bay but the flooding discharge would continue downstream into downtown Laconia. According to the files of the NHWRB and confirmed by the references, the maximum safe discharge capacity of the constricted channel in downtown Laconia is 2,600 cfs. Any discharge above this would cause substantial damage. There is a potential for loss of 4 or more lives in this area, especially of a breach occurred without warning. Surcharge storage on Winnisquam Lake would significantly attenuate the flooding conditions. Thus, no significant damages below Winnisquam are anticipated. Lakeport Dam was classified High Hazard based on excessive property damage and potential for loss of 4 or more lives in event of a breach. A detailed downstream hazard map can be seen in Appendix D.

SECTION 6
EVALUATION OF STRUCTURAL STABILITY

6.1 Visual Observations

The visual examination indicates the following potential structural problems:

(1) A minor sinkhole behind the training wall on the northwest side of the downstream channel which could lead to localized failure of the training wall if it is allowed to increase in size.

(2) An eroded area on the downstream southeast abutment training wall, if left uncorrected, could effect the integrity of the training wall.

(3) The surface spalling of the concrete walls of the intake channel to the stoplog spillway does not pose a threat to the stability of the dam.

6.2 Design and Construction Data

Available design drawings indicate that the dam rests on a sand foundation and that a steel sheet pile wall has been driven under the upstream side of the dam. The design drawings also show a three-layer graded drainage filter under the concrete gate structure. It is not possible to verify the existence of the sheet pile cutoff wall or the filter on the basis of the visual inspection alone.

6.3 Post Construction Changes

The dam was reconstructed in 1957-58. Files from the New Hampshire Water Resources Board (NHWRB) indicate that the Scott & Williams Canal was taken out and the stoplog bay constructed in its place sometime in 1967.

6.4 Seismic Stability

This dam is located in Seismic Zone 2 and, in accordance with the Phase I Guidelines, does not warrant seismic analysis.

SECTION 7
ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination indicates that Lakeport Dam is in good condition. Minor concerns are:

(1) Minor sinkhole behind the dry-stone-masonry training wall on the northwest side of the discharge channel.

(2) The eroded area on the downstream southeast abutment training wall.

(3) The surface spalling on the walls of the intake channel to the stoplog spillway.

b. Adequacy of Information. Available design data, combined with the results of the visual inspection, are adequate for the purposes of this Phase I inspection.

c. Urgency. The owner should implement the recommendations in 7.2 and 7.3 within two years after receipt of this Phase I report.

7.2 Recommendations

The owner should retain a professional engineer qualified in the design and construction of dams to:

(1) Repair the eroded area on the downstream southeast abutment training wall and the surface spalling on the walls of the intake channel to the stoplog spillway. Oral communication with the NHWRB has indicated that plans for these repairs are underway.

(2) Investigate the effects of the deteriorated tailrace on the integrity of the structure.

The owner should carry out the recommendations made by the engineer.

7.3 Remedial Measures

a. Operating and Maintenance Procedures. The owner should:

(1) Fill the sinkhole behind the dry-stone-masonry training wall on the northwest side of the downstream channel and any other sinkholes that may form in the future behind the training walls next to the downstream channel.

(2) Replace deteriorated stoplogs and walkway planking.

(3) All steel should be cleaned and painted.

(4) Visually inspect the dam and appurtenant structures once a month.


(5) Establish written operating and maintenance procedures.

(6) Engage a registered professional engineer qualified in the design and construction of dams to make a comprehensive technical inspection of the dam once every two years.

(7) Establish a surveillance program for use during and immediately after heavy rainfall, and also a downstream warning program to follow in case of emergency.

7.5 Alternatives

There are no practical alternatives to the recommendations and remedial measures given in Sections 7.2 and 7.3.



VISUAL INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT Lakeport Dam, NH

DATE July 9, 1980

TIME 9:00 AM

WEATHER Warm, sunny

| | | |
|------------|--------------|--------------|
| W.S. ELEV. | U.S. | DN.S. |
| | <u>504.0</u> | <u>496.2</u> |

PARTY:

- | | |
|-----------------------------------|----------------------------------|
| 1. <u>Warren Guinan (ANCo)</u> | 6. <u>Gary Kerr (NHWRB)</u> |
| 2. <u>Stephen Gilman (ANCo)</u> | 7. <u>Bob Fay (dam operator)</u> |
| 3. <u>Leslie Williams (ANCo)</u> | 8. <u>Harold Wilcox (ANCo)</u> |
| 4. <u>Greg Comstock (ANCo)</u> | 9. <u>John Falcione (ANCo)</u> |
| 5. <u>Ronald Hirschfeld (GEI)</u> | 10. _____ |

| PROJECT FEATURE | INSPECTED BY | REMARKS |
|--------------------------------|--------------------------------|---------|
| 1. <u>Hydrology/Hydraulics</u> | <u>L. Williams/G. Comstock</u> | |
| 2. <u>Structural Stability</u> | <u>S. Gilman</u> | |
| 3. <u>Soils & Geology</u> | <u>R. Hirschfeld</u> | |
| 4. <u>Electrical</u> | <u>H. Wilcox</u> | |
| 5. <u>Mechanical</u> | <u>J. Falcione</u> | |
| 6. _____ | | |
| 7. _____ | | |
| 8. _____ | | |
| 9. _____ | | |
| 10. _____ | | |

PERIODIC INSPECTION CHECKLIST

PROJECT Lakeport Dam, NH DATE July 9, 1980

PROJECT FEATURE Stoplog Structure NAME S. Gilman

DISCIPLINE Structural & Soils NAME R. Hirschfeld

| AREA EVALUATED | CONDITION |
|---|--|
| <p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p> <p>Southeast abutment wall d/s of stoplog structure</p> | <p>Stoplog structure at southeast abutment.</p> <p>Good</p> <p>Soil</p> <p>None</p> <p>None</p> <p>Top of concrete walls are spalled.</p> <p>Top logs - good condition Bottom logs - show deterioration and several are leaking. Steel supports - surface corroded.</p> <p>Bottom 3 feet of wall is badly eroded with reinforcing steel visible. Maximum depth of erosion is 6".</p> |

PERIODIC INSPECTION CHECKLIST

PROJECT Lakeport Dam, NH DATE July 9, 1980
 PROJECT FEATURE Outlet Works - Control NAME S. Gilman
 DISCIPLINE Structural NAME _____

| AREA EVALUATED | CONDITION |
|--|---|
| <u>OUTLET WORKS - CONTROL TOWER</u> | See Attached Appendix Notes |
| a. Concrete and Structural | |
| General Condition | Good |
| Condition of Joints | Good |
| Spalling | Minor surface erosion on bottom of downstream walls |
| Visible Reinforcing | |
| Rusting or Staining of Concrete | None visible |
| Any Seepage or Efflorescence | None visible |
| Joint Alignment | |
| Unusual Seepage or Leaks in Gate Chamber | Some leaking around end of gates |
| Cracks | None |
| Rusting or Corrosion of Steel | Minor spot rusting except in embedded gate supports which are surface rusted. |
| b. Mechanical and Electrical | |
| Air Vents | |
| Float Wells | |
| Crane Hoist | |
| Elevator | |
| Hydraulic System | |
| Service Gates | |
| Emergency Gates | |
| Lightning Protection System | None |
| Emergency Power System | 25kw ONAN Generator - good |
| Wiring and Lighting System | Good |

PERIODIC INSPECTION CHECKLIST

PROJECT Lakeport Dam, NH DATE July 9, 1980
 PROJECT FEATURE Overflow Spillway NAME S. Gilman
 DISCIPLINE Structural & Soils NAME R. Hirschfeld

| AREA EVALUATED | CONDITION |
|--|--|
| <u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u> | |
| a. Approach Channel | |
| General Condition | Good |
| Loose Rock Overhanging Channel | None |
| Trees Overhanging Channel | A few small trees overhang channel. |
| Floor of Approach Channel | Soil |
| b. Weir and Training Walls | |
| General Condition of Concrete | Good |
| Rust or Staining | None visible |
| Spalling | None visible |
| Any Visible Reinforcing | Southeast abutment downstream face eroded with exposed steel |
| Any Seepage or Efflorescence | Some on southeast downstream abutment wall. |
| Drain Holes | None visible |
| c. Discharge Channel | |
| General Condition | Good |
| Loose Rock Overhanging Channel | None |
| Trees Overhanging Channel | A few small trees overhang channel. |
| Floor of Channel | Timber-plank apron immediately downstream of dam is deteriorated and eroded. Soil and boulders farther downstream. |
| Other Obstructions | None |

PERIODIC INSPECTION CHECKLIST

PROJECT Lakeport Dam, NH DATE July 9, 1980

PROJECT FEATURE Service Bridge NAME S. Gilman

DISCIPLINE Structural NAME _____

| AREA EVALUATED | CONDITION | |
|---|--|---|
| <p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <p>Bearings</p> <p>Anchor Bolts</p> <p>Bridge Seat</p> <p>Longitudinal Members</p> <p>Underside of Deck</p> <p>Secondary Bracing</p> <p>Deck</p> <p>Drainage System</p> <p>Railings</p> <p>Expansion Joints</p> <p>Paint</p> <p>b. Abutment & Piers</p> <p>General Condition of Concrete</p> <p>Alignment of Abutment</p> <p>Approach to Bridge</p> <p>Condition of Seat & Backwall</p> | <u>Steel</u> | <u>Wood</u> |
| | <p>Good</p> <p>Not visible</p> <p>Not applicable</p> <p>Good condition - minor surface erosion</p> <p>Not applicable</p> <p>Not applicable</p> <p>Good condition</p> <p>Not applicable</p> <p>Good condition</p> <p>Not applicable</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> | <p>Good</p> <p>Surface rusted</p> <p>Not applicable</p> <p>Good condition</p> <p>See Deck</p> <p>None</p> <p>Many planks are deteriorated</p> <p>Not applicable</p> <p>None</p> <p>Not applicable</p> <p>Not applicable</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> <p>Good condition</p> |

APPENDIX NOTES
Lakeport Dam

Left (Southeast) Gate Channel

| | |
|--|---|
| Concrete Abutments | Good condition. Minor surface erosion at bottom of walls - exposing surface aggregate, $\frac{1}{2}$ " maximum depth at downstream of stoplog supports (2' up from bottom). |
| Steel Gate Supports d/s (embedded in concrete) | Bottom 4 feet rusted on surface. Remainder is painted with minor spot rusting. |
| Gates | Good condition. No evidence of corrosion or deterioration. Steel upstream face is surface rusted below water line. |
| Catwalk | Steel: Good condition. Paint: Good condition. |
| Super Structure | Good condition. No indication of corrosion or instability. |
| Gate Supports | Upstream steel is surface corroded. |
| Channel Bottom | Good condition. Minor surface erosion. |

Middle Gate Channel

| | |
|------------------------|--|
| Concrete Abutments | Downstream. Good condition. Minor surface erosion at bottom of walls, exposing coarse aggregate. $\frac{3}{8}$ " maximum depth erosion downstream of stoplog supports (2' up from bottom). Upstream. Good condition. General loss of surface laitance below water line. |
| Embedded Gate Supports | Good condition. Bottom 4' surface rusted. |
| Gates | Good condition. Some deterioration of downstream wood facing. Bottom 2 horizontal steel supports are surface rusted. Upstream face is surface rusted below water line. |

Middle Channel (continued)

Catwalk

Good condition. Minor spot surface corrosion.

Super Structure

Good condition. No indication of surface corrosion or instability.

Channel Bottom

Not visible because gate could not be closed completely.

Right Gate Channel (Northwest)

Same as middle and left gate channels.

Wood Deck Tail Race

Wood facing is deteriorated and eroded on surfaces and joints. No major loss of planking - all appear to be intact.

APPENDIX B
ENGINEERING DATA

NEW HAMPSHIRE WATER RESOURCES BOARD
Room 316, State House Annex
Concord, New Hampshire 03301

Dear:

In reply to your inquiry concerning the operation of Lake Winnepesaukee, a summary of the previous operations is presented. Also, the proposed operation of Lake Winnepesaukee is noted with other pertinent information.


Lakeport dam was constructed or reconstructed by the Winnepissiogee Lake Cotton and Woolen Manufacturing Company in 1851 for water power at the dam and conservation water storage for mills in Lowell and Lawrence, Massachusetts. The Company had been incorporated in 1831. This Company had to buy flowage rights at many points around the lake. The original owner of the dam sold the dam, flowage and water rights to Public Service Company of New Hampshire in 1943. In 1958, the State of New Hampshire purchased the Lakeport dam, flowage and water rights from Public Service Company of New Hampshire after it had rebuilt the old dam. Since 1958, Water Resources Board, an agency of the State of New Hampshire, has operated the dam with regard to both the downstream water users, downstream property adjacent to Winnepesaukee as well as shore property on the lake. Downstream water users pay the cost of operation, debt service and retirement over a thirty year period.

From 1943 to 1958, Public Service Company of New Hampshire operated the lake in its interest with due regard to lake and river interests

Water Resources Board offered advice as to discharges during critical periods which they generally followed.

Since 1958, Water Resources Board has transferred the emphasis to favor the shore interests but not at undue expense of the downstream water users and river front property.

In the springs of 1953 and 1954, very high lake levels and discharges were necessary. This Board requested and obtained an engineering study prepared for the Corps of Engineers in 1957. This study was entitled "Engineering Study and Report for Control of Flood Discharges on Winnepesaukee River, New Hampshire" by Penton G. Keyes Associates. This report estimated construction necessary to increase the flow capacity of Winnepesaukee River at \$4,398,000 with annual charges of \$155,500. This results in an unfavorable cost-benefit ratio. However, certain improvements have been undertaken to improve conditions such as increasing discharge capacity at the rebuilt Lakeport dam.

The planned operation from 1958 through 1967 lowers the lake  about two feet below "full" pond on March 1, allows it to rise to full or three inches over full on June 1. On July 1, the target level is "full" pond with gradual lowering due to discharge during July and August until the level reaches about one foot below "full" on Labor Day. This rate of lowering is continued through September and October with a level about 22 inches below full on November 1. From November 1 to March 1, the level is stabilized between 22 to 24 inches below full, runoff conditions permitting.

-3-

Possible revised operations would attempt to maintain the level of the lake between full and six inches below full between July 1 and Labor Day and twelve inches drop between ^{2nd} July 1 and November 1. During November and December, the lake would be lowered twelve inches to near the present first of year level. The winter and spring operation would not be changed.

There are minimum flow restrictions of 250 cubic feet per second in the deed the State has, *as well as by law under certain conditions.* Present channel conditions below Lakeport dam restrict the discharge to not over 2600 cubic feet per second which is possible only when downstream inflow has returned to normal.

For over twenty years, snow water surveys have been conducted on the drainage area for use in gauging the discharge to maintain proper lake levels.

From the chart of lake levels, in 1953, the level of the lake reached 505.80' above Mean Sea Level although the discharge was 2,110 cubic feet per second. In 1954, the lake reached 505.86' with 2450 cubic feet per second discharge. Tabulated damages on the lake for these two high levels were estimated to be more than \$250,000.

Also, from the chart, the 1941 level of the lake dropped to 500.63 feet above Mean Sea Level in December with the discharge limited to 20 cubic feet per second. From this ^{1941,} years, 1953 and 1954, it shows that the inflow into Lake Winnepesaukee varies greatly with resulting wide variations in summer levels. Evaporation alone takes about twenty inches off of Lake Winnepesaukee between June 1 and October 1 of most years. This averages over 300 cubic feet per second evaporated. In dry years, the discharge for the period is only 250 cubic feet per second.

There has been a law regulating maximum discharge from June 1 through September 15 to 250 cubic feet per second when the lake is below 502.4' above Mean Sea Level from 1911 through 1949 when the restriction was extended through October 15. This Board has seen that this law has not been violated.

Hurricane storms and heavy fall rains can raise the lake as much as seven and one-half in 4 days. ~~This is the main reason at least six~~ ^{that the lake level must be}

~~inches below full lake is seen by Labor Day.~~ However, discharges may be increased if at or near full lake to reduce the full impact of these storms. It is hoped that you will understand the complexity of operating

Lake Winnepesaukee for the benefit of all concerned. The number one

"bugaboo" is the variations in weather and precipitation. To have cut off

all discharge from Lake Winnepesaukee in 1965 between May 1 and September 1

would have raised the July 4 level from 502.84' to 503.55' and September 1

level from 501.82' to 503.13', which could not be done due to local regulations

and Federal Power Commission regulations.

End. Chart

George M. McBa, Jr.
Chairman

NEW HAMPSHIRE WATER CONTROL COMMISSION DATA ON RESERVOIRS & PONDS IN NEW HAMPSHIRE

LOCATION

AT DAM NO. 130.01

Town Laconia County Belknap

Stream Winnepesaukee R.-Outlet Lake Paugus

Basin-Primary Merrimack R. Secondary Winnepesaukee R.

Local Name Lakeport Dam

DRAINAGE AREA

Controlled 36.3 Sq. Mi.: Uncontrolled 0 Sq. Mi.: Total 36.3 Sq. Mi.

ELEVATION vs. WATER SURFACE AREA vs. VOLUME

| Point | Elevation Feet | Surface Area Acres | Volume Acre Ft. |
|------------------------|-------------------|--------------------------|--------------------|
| (1) Max. Flood Height | | | |
| (2) Top of Flashboards | 504.76 | 44,586 | |
| (3) Permanent Crest | 502.32 | | |
| (4) Normal Drawdown | 500.59 | | 7,190,000,000 |
| (5) Max. Drawdown | 494.55 | | 19,240,000 |
| (6) Original Pond | | | |

Base Used U.S.G.S.: Coef. to change to U.S.G.S. Base

RESERVOIR CAPACITY

| | Total Volume | Useable Volume |
|----------------------|--------------------|----------------|
| Drawdown |ft. |ft. |
| Volume | 18,240,000 cu. ft. |ac. ft. |
| Acre ft. per sq. mi. | | |
| Inches per sq. mi. | | |

USE OF WATER Recreation Storage for Industrial and Public Utility

OWNER P.S.Co. of N.H. and Int. Paper & Power Co. Winnepesaukee Lake

REMARKS

Tabulation By BLT Date 10-30-41

NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON DAMS IN NEW HAMPSHIRE

LOCATION

STATE NO. 130.01

Town Laconia : County Belknap
Stream Winnepesaukee R. - Outlet
Basin-Primary Merrimack R. : Secondary Winnepesaukee R.
Local Name Lakeport Dam
Coordinates—Lat. 43° 20' 17" N : Long. 71° 20' 17" W

GENERAL DATA

Drainage area: Controlled 363 Sq. Mi.: Uncontrolled 0 Sq. Mi.: Total 363 Sq. Mi.
Overall length of dam 300 ft.: Date of Construction prior to 1886 (1851)
Height: Stream bed to highest elev. 14 ft.: Max. Structure 11 ft.
Cost—Dam : Reservoir

DESCRIPTION Gravity-Split stone, concrete on earth

Waste Gates

Type
Number 4 : Size 6 ft. high x 6 ft. wide
Elevation Invert 8.29 : Total Area 144 sq. ft.
Hoist

Waste Gates Conduit

Number : Materials
Size ft.: Length ft.: Area sq. ft.

Embankment

Type
Height—Max. ft.: Min. ft.
Top—Width : Elev. ft.
Slopes—Upstream on : Downstream on
Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction
Length—Total (20, 6' bays) ft.: Net 127 ft.
Height of permanent section—Max. 11 ft.: Min. ft.
Flashboards—Type removable stop planks : Height 1.94 ft.
Elevation—Permanent Crest 502.32 : Top of Flashboard 504.26
Flood Capacity cfs.: cfs/sq. mi.

Abutments

Materials:
Freeboard: Max. 3.0 ft.: Min. ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER P. S. & International Paper & Power Co.

REMARKS

Tabulation By RLT Date 12/29/38
B&B21254 B-6

NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON DAMS IN NEW HAMPSHIRE

66

LOCATION

STATE NO. 130.01

Town Laconia : County Selknap
Stream Winnepesaukee River Outlet Lake Pagogus
Basin-Primary Merrimack R. : Secondary Winnepesaukee R.
Local Name Lakeport Dam
Coordinates—Lat. 43° 30' + 17,400 : Long. 71° 30' - 2900'

GENERAL DATA

367.10

Drainage area: Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total 360 Sq. Mi.
Overall length of dam 300 ft.: Date of Construction
Height: Stream bed to highest elev. 14' ft.: Max. Structure 11' ft.
Cost—Dam : Reservoir

DESCRIPTION Gravity— Split Stone— Concrete on earth

Waste Gates

Type
Number 4 : Size 6' ft. high x 6' ft. wide
Elevation Invert 8.29 : Total Area sq. ft.
Hoist

Waste Gates Conduit

Number : Materials
Size ft.: Length ft.: Area sq. ft.

Embankment

Type
Height—Max. ft.: Min. ft.
Top—Width : Elev. ft.
Slopes—Upstream on : Downstream on
Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction
Length—Total (20-6' bays) / 27 ft.: Net 125 120 ft.
Height of permanent section—Max. ft.: Min. ft.
Flashboards—Type Removable Stop Planks : Height 24" 1.94 ft.
Elevation—Permanent Crest 502.32 : Top of Flashboard
Flood Capacity 1025 cfs.: 5.2 cfs/sq. mi.

Abutments

Materials:
Freeboard: Max. 3.0' ft.: Min. ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER Winnepesaukee Lake Cotton & Woolen Mfg. Co.
Room 3511, 200 East 42nd St N Y City

REMARKS

*P.S. Co. of N.H. &
Int. Paper & Power Co.*

Tabulation By A.A.N. & R.L.T. Date December 29, 1938.

**NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON RESERVOIRS & PONDS IN NEW HAMPSHIRE**

LOCATIONAT DAM NO. 130.01Town Laconia : County BalknapStream Winnepesaukee River (Outlet Lake Pangu) PAUGUBasin—Primary Verrimack R. : Secondary Winnepesaukee R.Local Name Lakeport Dam**DRAINAGE AREA**367.10Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total 360 Sq. Mi.**ELEVATION vs. WATER SURFACE AREA vs. VOLUME**

| Point | Head Feet | Surface Area Acres | Volume Acre Ft. |
|--|---------------------------|--------------------|-----------------|
| (1) Max. Flood Height | | | |
| (2) Top of Flashboards | | | |
| (3) Permanent Crest | | | |
| (4) Normal Drawdown | (37) 1206 | 1206 | 1206 |
| (5) Max. Drawdown | (Lake Winnepesaukee) 1206 | 1206 | 1206 |
| (6) Original Pond | | | |
| Base Used: Coef. to change to U.S.G.S. Base Winnepesaukee 44,586 D.D. 3.7 | | | |

RESERVOIR CAPACITY

| | Total Volume | Useable Volume |
|----------------------|----------------|----------------|
| Drawdown | <u>3.7</u> ft. | ft. |
| Volume | ac. ft. | ac. ft. |
| Acre ft. per sq. mi. | | |
| Inches per sq. mi. | | |

USE OF WATER ConservationOWNER Winnepesaukee Lake Cotton & Woollen Mfg. Co.

Room 3511-200 East 42nd St. N Y City

REMARKS

Tabulation By A A N & R L T Date December 28, 1938

| | |
|-----------|---|
| Rec'd | |
| Jacobson | |
| Holmgren | ✓ |
| | ✓ |
| Return to | |
| Filed | |
| File No. | |

WATER CONTROL COMMISSION
STATE OF NEW HAMPSHIRE

Concord, New Hampshire

October 26, 1938.

Winnebago Lake Cotton & Mollen Mfg Co.,
100 E 42nd St.,
N Y City

RE: Lake Damage Outlet N. C. C. No. 130.01

Gentlemen:

In order that we may determine the magnitude and extent of the flood of September 21-24 just passed, we are requesting the various dam owners in the State to supply us with the following information:

1. Was this dam injured? Ans. No
2. If so, to what extent? Ans. _____
3. Did all flashboards go out? Ans. No
4. What was the maximum height of water over the permanent crest of spillway? Ans. Max. elevation 36.75 on Sept. 25th
Full Lake 44.00
5. At what day and hour did the maximum flood height reach your dam? Ans.

| | Sept 21 | Sept 22 | Sept 23 | Sept 24 |
|------|---------|---------|---------|---------|
| Flow | 500 cfs | 510 " | 500 " | 460 " |

| | Sept 25 | Sept 26 | Sept 27 | Sept 28 |
|------|---------|---------|---------|---------|
| Flow | 460 cfs | 510 " | 510 " | 500 " |
6. Any other interesting information regarding the flood or rain fall may be given on the back of this sheet, or attach sheets.

Will you please return this letter with as much information as you can give us as promptly as possible. A self-addressed envelope is attached hereto.

We thank you for your cooperation.

Very truly yours,

Richard S. Holmgren

Richard S. Holmgren
Chief Engineer

CDC:GMB
Enc.



State of New Hampshire
PUBLIC SERVICE COMMISSION
CONCORD

COMMISSIONERS
JOHN W. STORRS, CHAIRMAN
FRED H. BROWN
MAYLAND H. MORSE
CLERK-ACCOUNTANT
WILLIAM W. TIRRELL

June 4, 1929.

I-2255

Mr. John W. Storrs, Chairman,
N. H. Public Service Commission,
Concord, New Hampshire.

Dear Sir:

Re: Lakeport dam - Laconia.

On the ninth day of May, 1929, I visited the Lakeport dam at the outlet of Lake Paugus, as to the dam itself, there is no indication but that it is safe. At the easterly end of the dam there are three outlets or bays, these served certain industries in the past, the two westerly bays have not been used for some years and are closed by timber bulkheads, the easterly one served the Scott & Williams factory, the water flowing through this bay then through an open canal to the mill. A break in the canal wall some distance below the dam necessitated closing the bay by temporary sheet piling and resulted in the loss of water power to the mill.


I was informed that arrangements had been made with Scott & Williams whereby a reinforced concrete intake

(that could be closed by stop plank) was to be built in the easterly bay and that the canal would be restored, I was further informed that they intended to permanently close the two westerly bays by reinforced concrete bulkheads.

May 30, 1929, I was informed (on the ground) that it had been definitely settled to do as above stated and that work would be begun June 3, 1929. June 3, 1929, I was informed (by telephone) that work had begun.

Respectfully submitted,

N. H. PUBLIC SERVICE COMMISSION,


Samuel J. Lord,
Engineer.

SJL:PDW

PUBLIC SERVICE COMMISSION OF NEW HAMPSHIRE—DAM RECORD

I-5477

| | | | | | |
|---------------------------------------|--|--------------------------------|----------------------------|-----------|--|
| TOWN | LACONIA | TOWN NO. | 1 | STATE NO. | |
| RIVER STREAM | Winnepesaukee River - Outlet Lake Paugus | | | | |
| DRAINAGE AREA | 360 Sq. Mi. | POND AREA | | | |
| DAM TYPE | Gravity | FOUNDATION NATURE OF | Earth | | |
| MATERIALS OF CONSTRUCTION | Split Stone, Concrete | | | | |
| PURPOSE OF DAM | POWER—CONSERVATION—DOMESTIC—RECREATION—TRANSPORTATION—PUBLIC UTILITY | | | | |
| HEIGHTS, TOP OF DAM TO BED OF STREAM | Approx. 14' | TOP OF DAM TO SPILLWAY CRESTS | 3' | | |
| SPILLWAYS, LENGTHS | 127' | 4 - 6'x6' Gates | LENGTH OF DAM, approx. 10' | | |
| DEPTHS BELOW TOP OF DAM | 20 - 6' bays | | | | |
| FLASHBOARDS TYPE, HEIGHT ABOVE CREST | Removable stop planks 24" | | | | |
| OPERATING HEAD CREST TO N. T. W. | 9' ± | TOP OF FLASHBOARDS TO N. T. W. | | | |
| WHEELS, NUMBER KINDS & H. P. | 2 used - 4 not used 1 wheel for gate cover | | | | |
| GENERATORS, NUMBER KINDS & K. W. | | | | | |
| H. P. 90 P. C. TIME 100 P. C. EFF. | H. P. 75 P. C. TIME 100 P. C. EFF. | | | | |
| REFERENCES, CASES, PLANS, INSPECTIONS | See Case Nos. I-2231, I-2255, I-1916, I-2280 | | | | |

REMARKS: *Winnepesaukee Lake Cotton & Wadlen Mfg Co*
 OWNER: *International Hydro Electric Co.*
 CONDITION: Good
 MENACE: Yes. Will be subject to periodic inspection.

To the Public Service Commission:

The foregoing memorandum on the above dam is submitted covering inspection made Aug. 21, 1936, according to notification to owner dated Aug. 10, 1936, and bill for same is enclosed.

D. Waldo White
Chief Engineer

Aug. 22, 1936
Copy to Owner

NEW HAMPSHIRE WATER RESOURCES BOARD

INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

DAM

BASIN Winnepesaukee NO. 1 — I-5477 ^{953 USGS}
 RIVER Winnepesaukee MILES FROM MOUTH D.A.SQ.MI. 360 (370)
 TOWN Lancaster OWNER International Hydro-Elec. Co., Boston
 LOCAL NAME OF DAM Lakeport Dam (Lancaster - 504.20) (Winnepesaukee Co. - 504.20)
 BUILT 1902/1904 DESCRIPTION Gravity - Split St. - Concrete
on Earth Granite blocks bed

POND AREA-ACRES 1,205 800, DRAINAGE FT. 3.7 POND CAPACITY-ACRD FT. 161 000
 HEIGHT-TOP TO BED OF STREAM-FT. 14 MAX. MIN. 14
 OVERALL LENGTH OF DAM-FT. 300 MAX. FLOOD HEIGHT ABOVE CREST-FT. 14
 PERMANENT CREST ELEV. U.S.G.S. 502.32 LOCAL GAGE 492.48 500.00
 TAILWATER ELEV. U.S.G.S. 502.32 LOCAL GAGE 500.00
 SPILLWAY LENGTHS-FT. 127 FREEBOARD-FT. 3
 FLASHBOARDS-TYPE, HEIGHT ABOVE CREST 2 ft 10 in 5 ft 10 in
 WASTE GATES-NO. 4 6 6 6 6 6
 WIDTH MAX. OPENING 8.00 8.00 8.00 8.00 8.00 8.00
 DEPTH SILL BELOW CREST El. 492.48 El. 492.48 El. 492.48 El. 492.48 El. 492.48 El. 492.48

REMARKS Outlet Lakeport Dam
Condition Good

POWER DEVELOPMENT

UNITS NO. RATED HP HEAD FEET C.F.S. FULL GATE KW NAME
6 9 105 10 Scott Williams Inc.
7 105 10 Scott Williams Inc.
105 10 Scott Williams Inc.
160 10 HH. Wood & Co. USGS list.

USE Power Generation

REMARKS 170/1200 1 wheel for 9240 power
4 wheels not used
Plant information from F.P. Williams, Observer at Lakeport Dam.
Plant of dam can be obtained from N.H. Power Co., Boston.

DATE 8/21/36



HYDRO-ELECTRIC DIVISION
CHESTER S. COLSON
HYDRAULIC ENGINEER

INTERNATIONAL PAPER COMPANY

PERSHING SQUARE BUILDING
PARK AVE. & 42ND STREET

New York June 1, 1927

Subject: DAM AT LAKEPORT

New Hampshire Public Service Commission,
Concord, N.H.

Gentlemen:

As you requested in your letter of May 12th an inspection of the dam of the Lake Winnipiseogee Cotton & Woolen Company at Lakeport, N.H., was made on May 26th by Mr. Nelson of this office and Mr. Lord of your office.

This dam consists of a series of masonry piers about 8 feet by 20 feet in plan spaced from 20 to 23 feet on centers with timber stop logs between the piers and with four inch splined sheeting driven into the gravel on the upstream side to form the water seal. The masonry piers are built of squared stone with courses 16 or 18 inches deep, laid dry. A timber mat covers the whole area under and between the piers and extends several feet down stream from the piers.

The dam holds back a head of water of about 11 or 12 feet when Lake Winnipiseogee is full to the 44 inch mark.

The sheeting planks and some of the stop logs in the section of the dam East of the gates are decayed somewhat. The timber in the section between piers three and four (counting from the West end of the dam) is in the worst condition and we are now asking for tenders covering repairs to this section.

Mr. Charles J. Hayford, Mayor of Laconia and Mr. French, City Engineer of Laconia were present at the inspection and Mr. French said that if one of the timber sections between the piers in the dam gave way he feared that the foundations of the piers in the bridge at Depot Street which is located 50 or 60 feet up stream from the dam might be endangered by the scouring action of the water. As we have already in 1922 drawn as much as 1500 cubic feet per second from the Lake for a period of a week, we do not feel that the failure of one of the timber sections would endanger the bridge pier foundations, if they were properly built, as it is not likely that the discharge between two of the piers would amount to more than 1000 to 1200 cubic feet per second.

For our own best interests however, we wish to keep the dam in a serviceable condition, and we thank you for calling the matter to our attention.

Yours very truly,



INTERNATIONAL PAPER COMPANY

Chester S. Colson
H. M. R.

CHESTER S. COLSON
Hydraulic Engineer


EMN:R



PAUGUS



LOCATION PLAN

1" = 1 MILE







REVIEWED AND APPROVED
C. C. Gilman
Chas. T. Main, Inc.
8/2/57


| | | | |
|-------------|---------------------|------|--------|
| DESIGNED BY | CHAS. T. MAIN, INC. | DATE | 8/2/57 |
| DRAWN BY | CHAS. T. MAIN, INC. | DATE | 8/2/57 |
| CHECKED BY | CHAS. T. MAIN, INC. | DATE | 8/2/57 |
| APPROVED BY | CHAS. T. MAIN, INC. | DATE | 8/2/57 |

| | |
|---|--------|
| DAM AT LAKEPORT, N.H. LOCATION & PLOT PLANS | |
| PUBLIC SERVICE CO. OF NEW HAMPSHIRE ENGINEERING DEPARTMENT | 6803-7 |







SECTION A-A




SECTION E-E




SECTION B-B




SECTION F-F



SECTION C-C





SECTION G-G



SECTION D-D

| | | |
|----------|------|----|
| DESIGNED | DATE | BY |
| DRAWN | DATE | BY |
| CHECKED | DATE | BY |
| TRACED | DATE | BY |

| | |
|---|--------|
| DUN P. LAURENT M.E. SHOWING CONDITIONS DEC 50 PLAN & SECTIONS | |
| PUBLIC SERVICE CO. IN NEW HAMPSHIRE ENGINEERING DEPARTMENT | 6511-2 |









NOTES

COMPRESSIVE STRENGTH OF CONCRETE @ 28 DAYS IS 3500 PSI
BOND LENGTH FOR ALL REINFORCING BARS TO BE 40 DIA.
CONCRETE COVER ON ALL REINFORCING TO BE 3" MINIMUM EXCEPT AS NOTED
CHECK ALL ELECTRICAL DRAWINGS FOR EMBEDED MATERIAL

NOTE: BASE LINE
LOCATED ALONG EAST SIDE
OF EXISTING PIERS 5

DETAILS
SPILLWAY - PIER INTERFERING (Type AP3)
@ 1/4" = 1'-0" (1/2" = 1'-0")
TO ELEV 500.5




REVIEWED AND APPROVED
C. L. Goffman
Chas. T. Main, Inc.
8/2/57


| | |
|------------|-----------------------|
| PROJECT | DAM AT LAKEPORT, N.H. |
| DRAWN BY | C. L. Goffman |
| CHECKED BY | Chas. T. Main, Inc. |
| DATE | 8/2/57 |

| | |
|------------|-----------------------|
| PROJECT | DAM AT LAKEPORT, N.H. |
| DRAWN BY | C. L. Goffman |
| CHECKED BY | Chas. T. Main, Inc. |
| DATE | 8/2/57 |


| | | |
|-------------------------------------|------------------------|--------|
| PUBLIC SERVICE CO. OF NEW HAMPSHIRE | ENGINEERING DEPARTMENT | 6803-B |
|-------------------------------------|------------------------|--------|



Entry 505.31. Top Price
 Entry 509.22. Full Price
 Entry 500.95. Low Price
 334% w Gain. Entry 495.22



SECT C-C





SECT A-A

CORE DRILLING LOG

ROCKET ELEV
992.5

| ① | ② | ③ |
|-----|-----|-----|
| 0 | 0 | 0 |
| 1 | 1 | 1 |
| 2 | 2 | 2 |
| 3 | 3 | 3 |
| 4 | 4 | 4 |
| 5 | 5 | 5 |
| 6 | 6 | 6 |
| 7 | 7 | 7 |
| 8 | 8 | 8 |
| 9 | 9 | 9 |
| 10 | 10 | 10 |
| 11 | 11 | 11 |
| 12 | 12 | 12 |
| 13 | 13 | 13 |
| 14 | 14 | 14 |
| 15 | 15 | 15 |
| 16 | 16 | 16 |
| 17 | 17 | 17 |
| 18 | 18 | 18 |
| 19 | 19 | 19 |
| 20 | 20 | 20 |
| 21 | 21 | 21 |
| 22 | 22 | 22 |
| 23 | 23 | 23 |
| 24 | 24 | 24 |
| 25 | 25 | 25 |
| 26 | 26 | 26 |
| 27 | 27 | 27 |
| 28 | 28 | 28 |
| 29 | 29 | 29 |
| 30 | 30 | 30 |
| 31 | 31 | 31 |
| 32 | 32 | 32 |
| 33 | 33 | 33 |
| 34 | 34 | 34 |
| 35 | 35 | 35 |
| 36 | 36 | 36 |
| 37 | 37 | 37 |
| 38 | 38 | 38 |
| 39 | 39 | 39 |
| 40 | 40 | 40 |
| 41 | 41 | 41 |
| 42 | 42 | 42 |
| 43 | 43 | 43 |
| 44 | 44 | 44 |
| 45 | 45 | 45 |
| 46 | 46 | 46 |
| 47 | 47 | 47 |
| 48 | 48 | 48 |
| 49 | 49 | 49 |
| 50 | 50 | 50 |
| 51 | 51 | 51 |
| 52 | 52 | 52 |
| 53 | 53 | 53 |
| 54 | 54 | 54 |
| 55 | 55 | 55 |
| 56 | 56 | 56 |
| 57 | 57 | 57 |
| 58 | 58 | 58 |
| 59 | 59 | 59 |
| 60 | 60 | 60 |
| 61 | 61 | 61 |
| 62 | 62 | 62 |
| 63 | 63 | 63 |
| 64 | 64 | 64 |
| 65 | 65 | 65 |
| 66 | 66 | 66 |
| 67 | 67 | 67 |
| 68 | 68 | 68 |
| 69 | 69 | 69 |
| 70 | 70 | 70 |
| 71 | 71 | 71 |
| 72 | 72 | 72 |
| 73 | 73 | 73 |
| 74 | 74 | 74 |
| 75 | 75 | 75 |
| 76 | 76 | 76 |
| 77 | 77 | 77 |
| 78 | 78 | 78 |
| 79 | 79 | 79 |
| 80 | 80 | 80 |
| 81 | 81 | 81 |
| 82 | 82 | 82 |
| 83 | 83 | 83 |
| 84 | 84 | 84 |
| 85 | 85 | 85 |
| 86 | 86 | 86 |
| 87 | 87 | 87 |
| 88 | 88 | 88 |
| 89 | 89 | 89 |
| 90 | 90 | 90 |
| 91 | 91 | 91 |
| 92 | 92 | 92 |
| 93 | 93 | 93 |
| 94 | 94 | 94 |
| 95 | 95 | 95 |
| 96 | 96 | 96 |
| 97 | 97 | 97 |
| 98 | 98 | 98 |
| 99 | 99 | 99 |
| 100 | 100 | 100 |



AN OF WEST BANK
SCALE 1"=10'

SECT X-X & Y-Y
SCALE 1"=3'

REVIEWED AND APPROVED

C. L. Galloway
Chas. T. Main, Inc.
8/2/57


| REVISION | DATE |
|---------------------|--------|
| 1. Revised to show | 8/2/57 |
| 2. Revised to show | 8/2/57 |
| 3. Revised to show | 8/2/57 |
| 4. Revised to show | 8/2/57 |
| 5. Revised to show | 8/2/57 |
| 6. Revised to show | 8/2/57 |
| 7. Revised to show | 8/2/57 |
| 8. Revised to show | 8/2/57 |
| 9. Revised to show | 8/2/57 |
| 10. Revised to show | 8/2/57 |

COMPARISON DRAWINGS 6-5-57 3-1-58 11 3586/68


DAM AT LAKEPORT N.H.
MISCELLANEOUS DETAILS

PUBLIC SERVICE CO. OF NEW HAMPSHIRE
ENGINEERING DEPARTMENT


6803-12




ORIGINAL PLAN VIEW
SCALE 1"=20'





SECT. A-A
SCALE 1"=5'




PLAN DURING CONSTRUCTION
SCALE 1"=20'



SECT. B-B
SCALE 1"=5'




DURING CONSTRUCTION
SCALE 1"=20'




FILES 1, 2 & 3 CAPPED
WITH CONCRETE AFTER
LOOSE MATERIAL
HAS BEEN REMOVED

COMPLETED PLAN VIEW
SCALE 1"=20'



SECT. B-B
SCALE 1"=5'




SECT. C-C
SCALE 1"=5'


REVIEWED AND APPROVED
C. E. Gillingham
Chas. T. Main, Inc.
8/2/57

| | | | |
|----------|------|----|-------|
| DESIGNED | DATE | BY | CHKD. |
| DRAWN | DATE | BY | CHKD. |
| TRACE | DATE | BY | CHKD. |

CONSTRUCTION DRAWINGS 6803-70, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100


| | |
|---|--------|
| DAM AT LAKEPORT, N.H. | |
| CONSTRUCTION | |
| ON EAST BANK OF RIVER | |
| PUBLIC SERVICE CO. OF NEW HAMPSHIRE ENGINEERING DEPARTMENT SCALE 1"=20' DATE 8/2/57 | 6803-3 |






DAM AT LAKEPORT, N.H.
GATE DISCHARGES
 PUBLIC SERVICE CO. NEW HAMPSHIRE
 1938 6803 - 26

APPENDIX C
PHOTOGRAPHS



| | | | |
|---|--|-------------------------------------|--|
| Anderson-Nichols & Co., Inc. | | U.S. ARMY ENGINEER DIV. NEW ENGLAND | |
| CONCORD | | CORPS OF ENGINEERS | |
| NEW HAMPSHIRE | | WALTHAM, MA. | |
| NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS | | | |
| LAKEPORT DAM | | | |
| PHOTO INDEX | | | |
| WINNIPESAUKEE RIVER | | NEW HAMPSHIRE | |
| | | SCALE: NOT TO SCALE | |
| | | DATE: AUGUST 1980 | |



July 9 , 1980
Photo 2 - Looking across the crest of the dam from
the southeast abutment.



July 9 , 1980
Photo 3 - View of the upstream face of the dam from
the Elm Street Bridge.



July 9, 1980
Photo 4 - Looking at the stoplog spillway structure.



July 9, 1980
Photo 5 - View of the downstream face of the overflow spillway.




July 9, 1980
 Photo 6 - View of the downstream face of the dam
 from the northwest abutment. Note the
 side channel at the far end of dam.



July 9, 1980
 Photo 7 - Looking at the gated section of the dam.



July 9, 1980
Photo 8 - Looking at the northwest abutment.



July 9, 1980
Photo 9 - View of the surface spalling on the
intake channel to the stoplog spillway.




July 9, 1980
 Photo 10 - View of the surface spalling on the
 southeast end of the intake channel
 to the stoplog spillway.



July 9, 1980
 Photo 11 - View of the eroded area on the down-
 stream southeast abutment training
 wall.



July 9, 1980
 Photo 12 - Looking at the downstream side of the gate structure nearest the northwest abutment. Note leakage around end of gate.



July 9, 1980
 Photo 13 - Looking upstream from the crest of the dam.



July 9 , 1980
 Photo 14 - Looking at the southeast downstream
 channel masonry wall.




July 9 , 1980
 Photo 15 - Looking at the northwest downstream
 channel masonry wall.



July 9 , 1980
Photo 16 - View of the sinkhole noted in the fill
behind the training wall on the north-
west side of the discharge channel.

APPENDIX D
HYDROLOGIC AND HYDRAULIC COMPUTATIONS



**NATIONAL PROGRAM OF INSPECTION
OF NON-FED. DAMS**

**LAKEPORT DAM
LACONIA, NEW HAMPSHIRE
REGIONAL VICINITY MAP**


AUGUST 1980

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS


ANDERSON-NICHOLS & CO., INC.



CONCORD, NH

SCALE IN MILES



MAP BASED ON U.S.G.S. 1:250,000 SERIES
TOPOGRAPHIC MAPPING, NK 19-1 PORTLAND,
ME, N.H. 1956 REVISED 1972.







NG-1
Diagrammatic Coding prepared by
Lester Hayes Associates
Dated January 98

LEGEND

1. The first step is to identify the problem or question that needs to be answered. This involves understanding the context and the specific requirements of the task.


0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000 1001 1002 1003 1004 1005 1006 1007 1008 1009 1010 1011 1012 1013 1014 1015 1016 1017 1018 1019 1020 1021 1022 1023 1024 1025 1026 1027 1028 1029 1030 1031 1032 1033 1034 1035 1036 1037 1038 1039 1040

| | | |
|--|---|-------------------------------|
| | MERRIMACK RIVER FLOOD CONTROL RIVER PLAN & PROFILE LAKEPORT | |
| PROJECT NUMBER 0001-1 | WINNIPESAUKEE RIVER NEW HAMPSHIRE | APRIL, 1979 |
| DESIGNED BY ANDERSON NICHOLS & COMPANY INC. | DRAWN BY JAMES W. HARRIS | CHECKED BY JAMES W. HARRIS |



2

NOTE: This delineation has been revised to reflect the downstream hazard conditions which may result with a breach of Lakeport Dam.



JOB NO. 3273-24 Lakeport Dam

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

BREACH ANALYSIS - Assume breach to occur with water surface at top of dam (504.32' NGVD) to determine downstream hazard potential.

Assume WSEL @ 504.32' NGVD

Downstream invert (gate section) = 495.22' NGVD

Downstream invert (spillway section) = 495.9' NGVD

$$Q_E = \frac{2}{27} W_b \sqrt{g} y_0^{3/2} \quad \text{where: } W_b = \text{breach width}$$

$$g = 32.2 \text{ ft/sec}^2$$

$$y_0 = \text{depth at breach}$$

Breach could be assumed to occur at either the gated section (Q_{p1}) or the spillway section (Q_{p2}) of the dam.

Gated Section

$$W_b = 78'$$

$$y_0 = 504.32 - 495.22 = 9.1'$$

$$Q_{p1} = \frac{2}{27} (78) (\sqrt{32.2}) (9.1)^{3/2}$$

$$Q_{p1} = 3600 \text{ cfs}$$

Spillway Section

$$W_b = 85'$$

$$y_0 = 504.32 - 495.9 = 8.4'$$

$$Q_{p2} = \frac{2}{27} (85) (\sqrt{32.2}) (8.4)^{3/2}$$

$$Q_{p2} = 3480 \text{ cfs} + 250 \text{ cfs} = 3730 \text{ cfs}$$

↓ discharge through gated section

Assume normal operation of gates at Lakeport and normal elevation of Opechee Bay ($\approx 492'$ NGVD). Utilizing the HEC-2 backwater runs from Reference = 1 (Laconia, FIS), the 100-year profile of $Q = 3,500$ cfs provides a reasonable estimate of downstream damages caused by Breach Q_{p1} or Q_{p2} . A breach discharge of this magnitude could cause an increase in stage

TABLE VI-1

GAGE HEIGHTS AND CAPACITY OF LAKE WINNIPESAUKEE

| Elev. ft. above msl | Gage height feet | Capacity in millions of cubic feet | Cumulative usable capacity in millions of cubic feet | |
|-------------------------------|------------------------|--|--|---------------------|
| | | | <u>above 504.32</u> | <u>above 500.00</u> |
| 505.00 | 5.00 | 19,850 | 455,700 | * |
| Report Top of Dam → 504.32 | 4.32 | (est.)* 18,440 | 423,300 | 7,220 |
| 504.00 | 4.00 | 17,840 | 409,550 | 6,620 |
| 503.00 | 3.00 | 15,840 | | 4,620 |
| 502.00 | 2.00 | 13,880 | | 2,660 |
| 501.50 | 1.50 | 12,900 | | 1,680 |
| 501.00 | 1.00 | 11,930 | | 710 |
| 500.65 | 0.65 | (est.) 11,220 | | 0 |
| 500.00 | 0.00 | 10,020 | | — |


* Storage capacity above Elev. 504.32 ft. is temporary or surcharge storage.

The watershed of Lake Winnepesaukee is 363 square miles. Using the data contained in Figures 2-1, 2-2, and 2-3, the table below shows the estimated daily runoff. (Evaporation from the lake surface would reduce the usable portion of this runoff.)

| <u>Type</u> | <u>Runoff in mgd</u> |
|--------------------|--------------------------|
| Annual mean runoff | 385 |
| 95% dry year | 200 |
| 1965 | 175 |

As the Coastal Area average daily requirement in 2020 is only 140 mgd, it seems reasonable to assume that natural runoff alone would support the area's water supply requirements. At some future date, however, augmentation will become necessary. The brief analysis described below discusses augmentation from the Pemigewasset River and gives

Lake Winnepesaukee - USGS @ Lakesport
USABLE STORAGE / ELEVATION



JOB NO. 3273-24 Lakeport Dam,
Laconia, N.H.SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4" SCALE

DAM : Lakeport
Drainage Area : 363 mi²
Hydraulic Height : $504.32 - 495.22 = 9.1'$ } Size - Large
Storage Capacity : 165,700 ac-ft (usable) } based on storage
D/S Hazard : High
Test Flood Range : PMF
Chosen Test Flood : PMF

Lakeport Dam controls the water level and outflow from Lake Winnepesaukee, a large recreational lake owned and controlled by the State of New Hampshire Water Resources Board (NHWRB). Numerous studies have been done on Lakeport Dam and the Lake Winnepesaukee basin. The following specific studies were evaluated and pertinent sections were utilized in the compilation of data significant to this report:

Ref. 1. Laconia, N.H. Flood Insurance Study (FIS) performed by Anderson-Nichols & Co., Inc., Concord, NH, 1978.

Ref. 2. "Lakeport Dam, Inspection and Analysis Report", July 1978, by Chas. T. Main, Inc., Boston, Mass.

Ref. 3. "Hydraulic Engineering Analysis for Evaluating Flood Stage Reduction on the Winnepesaukee River, New Hampshire", 1978, by Anderson-Nichols & Co., Inc., Concord, N.H.


In addition to these studies, additional data and information was obtained from the files of the NHWRB.

A cross section follows which defines the pertinent features and elevations of the dam.

JOB NO. 3273-24

SQUARES 1/4" SCALE 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 2 30

Cross section of existing Lakeport Dam from downstream looking upstream.



507 505 503 501 499 497 495

6-D Vertical Scale: 1" = 2'

JOB NO. 3273-24 Lakeport Dam

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

The PMF analysis performed in Reference 2, performed by Chas. T. Main in July 1978, was evaluated for use in this report. After examination of the backup, it was determined that the analysis was a detailed study of the basin and probably reflects more accurately the actual basin characteristics than that which would be performed in a Phase I analysis using the COE "guide curves". The study was reviewed and the results deemed reasonable. Concurrence was given by the Corps for use of this PMF analysis in this Phase I inspection report.

Following is the complete H/H appendix as seen in the Chas. T. Main study.

Backup taken from:
"Lakeport Dam, Inspection and Analysis
Report", July 1978, by Chas T. Main

HYDROLOGY

Any catchment such as Lake Winnepesaukee and its contiguous area that is comprised of hydrologically diverse elements must be analyzed for the Probable Maximum Flood by the rationale of their individual hydrologic response characteristics. To accomplish this, the subject catchment was separated into the lake area, 73 sq. mi., and the peripheral contiguous area, 290 sq. mi. The hydrologic response criteria for separation were direct rainfall on the lake area and a typical overland flow runoff pattern for the remaining area.

PROBABLE MAXIMUM PRECIPITATION: (PMP)

The joint U. S. Corps of Engineers - U. S. Weather Bureau Hydrometeorological Report #33 indicated a 200 sq. mi. - 24 hour "all season envelope" value of 18 inches for the project locus. This value was adjusted downward by about 8 percent to 16.5 inches as a trajectory correction for storm centering on the catchment. Both the total catchment area and type of storm assumed, indicated that a forty-eight hour storm would be typical for the extreme event.

To compute the depth-area-duration (DAD) values to be used in this study, the DAD values shown in Plate E-III from the Corps of Engineers for the storm of 2-4 November 1927 were utilized. Semi-logarithmic plots of the ratio of these historic values to the historic 200 sq. mi. - 24 hour value were made (see table E-1) and the ratios for the 73 sq. mi. and the total catchment of 363 sq. mi. were obtained. It was assumed that the PMP isohyetal pattern would be superimposed on the catchment so that both the total area, 363 sq. mi. and the lake area, 73 sq. mi., would experience their respective theoretical Probable Maximum Precipitation. This assumption permitted the computation of the PMP values for the various durations from a volume basis i.e. the PMP volume for a particular interval for 363 sq. mi. minus the 73 sq. mi. PMP volume divided by the remaining area, 290 sq. mi. would give the PMP value for that interval for 290 sq. mi. The derived PMP values are shown in Table E-2.

A smoothed cumulative rainfall curve with percent of total storm time versus percent of total PMP was used to derive two hour incremental and critically arrayed PMP values for both the 73 sq. mi. and 290 sq. mi. sub areas. To these values for the 290 sq. mi. were applied an assumed initial loss of 0.5 inches and a loss rate up through the 30th hour of 0.1 inches per hour for a total runoff of 13.6 inches. The two hour Probable Maximum Rainfall excess values are shown in Table E-3. The two hour incremental Probable Maximum Precipitation values for the Lake Area, 73 sq. mi., are also shown in Table E-3.

UNIT HYDROGRAPH DERIVATION:

The continuous drainage area of 290 sq. mi. is essentially elliptical and is drained by many radial streams. There are no stream gages for flow measurement on any of these streams, a fact which necessitated the use of the U. S. Soil Conservation Service's Triangular Unit Hydrograph Methodology. To accomplish this derivation, the major and minor axes of the enveloping ellipse were drawn and the hydrograph parameters of area, i.e., average elevation, length of longest water course and rim elevation were measured. Triangular Unit hydrographs which produced one inch of runoff from two hours of rainfall excess were then computed for each of the four sub areas.

Each of these triangular unit hydrographs were then ratioed up to a triangular unit by hydrograph for 290 sq. mi. with the peak being increased as the square root of the ratio of the drainage areas. These four new triangular hydrographs for 290 sq. mi. were plotted and a composite unit hydrograph derived on the basis of the critical time to peak. This derived 290 sq. mi. triangular hydrograph was then normalized to a conventionally shaped unit hydrograph using standard ratios of times and discharges. The ordinates of this normalized hydrograph are given in Table E-4.


PMP INFLOW FLOOD HYDROGRAPH:

The rainfall excess values computed for the 290 sq. mi. area were then combined in a time-discrete method with the derived 290 sq. mi. unit hydrograph to produce the Probable Maximum Flood Inflow hydrograph from the contiguous area. This hydrograph had a peak of 218,000 cfs and a total runoff volume of 13.6 inches. See Plate E-1. As is customary in hydrologic studies of this nature, MAIN customarily performs routine checking procedures. The Nuclear Regulatory Commission has published a series of Probable Maximum Flood Peak Isopleths for various size drainage areas. Using curve fitting procedures, the PMF peak for 290 sq. mi. was found to be 198,500 cfs and had a Creager C of 87.7. This peak value is about 91 percent of the peak computed by MAIN and can be considered a check. The Creager C computed by MAIN was 96.8 which is a very reasonable value for an event of this rarity and severity. It must be noted that these checks are only for order of magnitude.

This PMF flood hydrograph was then combined with the temporal PMP values for the lake area to produce a time discrete volume curve for the lake for routing purposes.

Backwater curve analysis by Anderson-Nichols, consulting engineers of Concord, New Hampshire, indicated a four (4) ft. drop of water level from Lake Winnepesaukee to Lakeport Dam for a discharge of 5200 cfs and water level El. 505.3 at the dam. We used that result to obtain a 3.8 ft. drop to Lakeport Dam for the Lake Winnepesaukee PMF maximum water level of El. 509.0. PMF discharge at Lakeport Dam has 5100 cfs. (See Plate E-1).

Since the all season PMP envelope was the September value, a month end lake level duration curve for the lake was computed. The end of August lake volume, equaled or exceeded 25 percent of the time, was selected as a stringent value for this rare event. This value resulted in a starting elevation of 503.56.



NEW HAMPSHIRE WATER RESOURCES BOARD
CONCORD, NEW HAMPSHIRE
LAKEPORT DAM


HYDROGRAPHS
PROBABLE MAXIMUM FLOOD ROUTING

DATE JULY, 1978

MAIN

CLIENT JOB PLA
1318 12 E-I

D-13



NOTE: DISCHARGE BELOW EL. 504.2 IS FULL CAPACITY OF 3 GATES. .
 DISCHARGE ABOVE EL. 504.2 IS FULL CAPACITY OF 3 GATES PLUS
 FLOW OVER DAM.

NEW HAMPSHIRE WATER RESOURCES BOARD
 CONCORD, NEW HAMPSHIRE
 LAKEPORT DAM

PROJECT DISCHARGE CURVE


MAIN

DATE DEC. 1977

| CLIENT | JOB | PLATE |
|--------|-----|-------|
| 1318 | 12 | E-II |

D-14

STORM STUDIES - PERTINENT DATA SHEET



Storm of 2-4 November 1927
 Assignment MA 1-27

Location Maine to Pennsylvania
 Study Prepared by:
 North Atlantic Division
 New York District Office

Part I Reviewed by H. M. Ser
 Weather Bureau, 2/11/46

Part II Approved by Office, Ch
 of Engineers for Distributi
 of Factual Data, 10/29/48

Remarks: Center at
 Kinsman Notch, N. H.
 Dewpt. 50°- Ref. Ft. 250 SS
 Grid C-3

DATA AND COMPUTATIONS COMPILED

PART I

Preliminary isohyetal map, in 2 sheet, scale 1: 1,000,000

Precipitation data and mass curves:

(Number of Sheets)

| | |
|--|-----|
| Form 5001-C (Hourly precip. data) | 1 |
| Form 5001-B (24-hour " " " ") | 523 |
| Form 5001-D (" " " ") | 4 |
| Misc. precip. records, meteorological data, etc. | 1 |
| Form 5002 (Mass rainfall curves) | 90 |

PART II

Final isohyetal maps, in 2 sheet, scale 1:1,000,000

Data and computation sheets:

| | |
|--|----|
| Form S-10 (Data from mass rainfall curves) | 12 |
| Form S-11 (Depth-area data from isohyetal map) | 2 |
| Form S-12 (Maximum depth-duration data) | 9 |
| Maximum duration-depth-area curves | 1 |
| Data relating to periods of maximum rainfall | 3 |

MAXIMUM AVERAGE DEPTH OF RAINFALL IN INCHES

| Area in Sq. Mi. | Duration of Rainfall in Hours | | | | | | | |
|-----------------|-------------------------------|------|------|------|------|------|------|------|
| | 6 | 12 | 18 | 24 | 30 | 36 | 48 | 60 |
| 10 | 7.6 | 10.6 | 11.7 | 12.0 | 12.6 | 13.7 | 11.0 | 11.0 |
| 100 | 5.8 | 8.3 | 8.8 | 9.2 | 9.5 | 10.1 | 10.3 | 10.3 |
| 200 | 5.7 | 8.2 | 8.6 | 8.8 | 9.0 | 10.0 | 10.2 | 10.2 |
| 500 | 5.5 | 7.9 | 8.2 | 8.3 | 8.5 | 9.0 | 9.2 | 9.2 |
| 1,000 | 4.8 | 7.3 | 7.7 | 7.8 | 8.2 | 8.8 | 8.9 | 8.9 |
| 2,000 | 4.0 | 6.4 | 7.0 | 7.3 | 7.9 | 8.1 | 8.2 | 8.2 |
| 5,000 | 2.7 | 4.8 | 6.1 | 6.7 | 7.2 | 7.7 | 7.9 | 7.9 |
| 10,000 | 2.3 | 4.0 | 5.5 | 6.3 | 6.7 | 7.0 | 7.3 | 7.3 |
| 20,000 | 2.0 | 3.5 | 4.7 | 5.3 | 5.8 | 6.2 | 6.4 | 6.4 |
| 50,000 | 1.6 | 2.8 | 3.6 | 4.1 | 4.5 | 4.9 | 5.1 | 5.1 |
| 60,000 | 1.4 | 2.5 | 3.3 | 3.8 | 4.2 | 4.6 | 4.8 | 4.8 |

APPENDIX E

INFORMATION AS
CONTAINED IN THE NATIONAL
INVENTORY OF DAMS